Zava Builders · 1200 Granite Way, Suite 400, Columbus, OH 43215 · 614-555-0142

Change Order

CO-1041 · Riverside Corporate Office (ZB-2026-014)

Change order	Project	Vendor	Submitted	Accepted
CO-1041	Riverside Corporate Office ZB-2026-014	Contoso Concrete 88 Quarry Road, Delaware, OH 43015	22 October 2026	26 October 2026

Polished concrete floor finish, levels 1 to 4

Contoso Concrete requests the following change to the Work under the Agreement dated 12 May 2026 for Riverside Corporate Office, project ZB-2026-014. Zava Builders accepts the stated scope, phase-specific calendar-day adjustments and net price upon the acceptance recorded below; the detailed description in this document is attached to and forms part of this change order.

Change 1 · Phase 3: Concrete floors and slabs

As contracted	As changed by this change order
• Place approximately 92,000 sq ft of 4,000 psi reinforced floor concrete on levels 1 to 4, including the atrium floor, to S-301 through S-304 and ACI 318. • Provide the sealed broom-finish surface specified on A-601 under ACI 302.1R, with the original resilient flooring allowance in Interior build-out. • Cure and protect the floor plates to ACI 308.1 and verify substrate readiness for the scheduled resilient flooring under ASTM F710. • Maintain slab thicknesses, reinforcement, joints and service penetrations as detailed on the structural drawings.	• Retain approximately 92,000 sq ft of 4,000 psi reinforced floor concrete and all original slab geometry under S-301 through S-304 and ACI 318. • Replace the sealed broom finish with a ground and polished 800-grit finish on levels 1 to 4, including the atrium floor, with densifier and two coats of guard under revised A-601. • Release each slab for grinding only after it reaches 28-day strength; polishing of a level shall wait until the level above has been poured, with no above-level hold on the uppermost floor. • Remove the resilient flooring allowance from Interior build-out in the affected floor areas and protect the exposed polished slabs as the final floor finish.

Added work

- Prepare and approve a representative 100 sq ft polished-finish mockup showing exposed aggregate, edge treatment and guard appearance under revised A-601.
- Grind approximately 92,000 sq ft through nominal 30, 80, 200 and 400 metal-bond preparation stages, with local repairs at surface defects before final polishing.
- Polish approximately 92,000 sq ft through the approved resin-bond sequence to 800-grit, including

edges at columns and the atrium perimeter.

- Apply compatible densifier at the approved coverage rate and two coats of guard over the complete polished floor area.
- Provide dust extraction, slurry collection, protected travel routes and temporary protective coverings over completed floors.
- Coordinate the affected resilient-flooring allowance deletion with the interior trade; carry the associated credits within the net adjustment stated here.

Deleted work

- Delete the sealed broom-finish treatment and its original sealer in the 92,000 sq ft polished-finish area.
- Delete the resilient flooring allowance over the affected slabs from Interior build-out; the net pricing includes this coordinated deletion without a separate duplicate charge or credit.

Work that remains as contracted

- The 4,000 psi slab concrete, reinforcement, structural thicknesses, joints and penetration locations remain as contracted.
- Office partitions, conference-suite ceilings, doors and wall finishes remain within the original Interior build-out scope.
- Structural frame and envelope assemblies remain unchanged.

Reason

Owner's design team revised the interior finish schedule to expose the structural slab on all levels; the polished finish removes the resilient flooring allowance from the interior build-out but adds grinding, densifying and curing time to the slab phase. The final visible floor becomes the structural slab itself, requiring a coordinated finish mockup, controlled grinding access and protection in lieu of covering the slab with the originally allowed resilient flooring.

Schedule impact on this phase: 21 calendar days against the existing schedule

The scheduled duration of Phase 3, Concrete floors and slabs, increases by twenty-one (21) calendar days against the existing schedule. Each level requires 3 to 4 additional days of grinding and polishing after the slab reaches 28-day strength; polishing cannot proceed on a level until the level above is poured, where one exists. Across the four levels, curing-release constraints, access sequencing and finish operations add three weeks to this phase. This adjustment applies to Phase 3 only and states no revised phase date.

Cost

Item	Amount
Labor: 2 finishing crews of 4 persons over 14 shifts, including edge finishing and the coordinated resilient-flooring labor credit	$18,000
Materials: densifier and two coats of guard for 92,000 sq ft, repair filler and protective coverings, net of deleted sealer and resilient-flooring allowance materials	$22,000

Equipment: planetary grinders, 800-grit polishing tooling and dust extraction for the four-level sequence, net of deleted finish equipment	$8,000
Change in contract sum for this phase	**$48,000**

Summary of this change order

Phases changed: Phase 3. Schedule impact: 21 calendar days in total across the changed phases, each against its own existing schedule. Change in contract sum: $48,000.

Phases that depend on a changed phase are adjusted in the project schedule record after acceptance; their managers are notified by the Contractor.

Contract sum and contract time

Original contract sum	$6,400,000
Net change by previously accepted change orders	$0
Contract sum prior to this change order	$6,400,000
This change order	$48,000
New contract sum	**$6,448,000**

Contract time: The scheduled duration of Phase 3 is increased by twenty-one (21) calendar days. After acceptance, Zava Builders adjusts the dates of dependent phases in the Schedule Record under the existing dependencies and notifies their vendors in writing.

Terms

- Upon authorised acceptance, this change order amends the Agreement only for the work, phase-specific time adjustments and Contract Sum adjustment expressly stated herein.
- The net adjustment is full compensation for this change, including additions, deletions, coordination, overhead and profit; no separate duplicate recovery is due for the stated changed work.
- After acceptance, Zava Builders shall adjust dependent phases in the Schedule Record according to existing dependencies and notify the affected vendors in writing; the phase-specific adjustments do not independently establish a revised project completion date.
- Pricing is valid for 30 days from submission.
- Except as expressly amended, all other Agreement terms, scope requirements, inspections and warranties remain unchanged.
- The detailed as-contracted, as-changed, added, deleted and unchanged work descriptions, reasons, schedule impacts and cost breakdowns above constitute the attached description and are integral to this change order.

Submitted by
Luis Herrera, Operations Manager,
Contoso Concrete
22 October 2026

Accepted for Zava Builders by
Anissa Carvalho, Project Manager,
Zava Builders
26 October 2026

All companies, people, addresses and figures in this document are fictional, created for a product demonstration.