Zava Builders · 1200 Granite Way, Suite 400, Columbus, OH 43215 · 614-555-0142

Change Order

CO-2007 · Harbor Logistics Center (ZB-2026-017)

Change order	Project	Vendor	Submitted	Accepted
CO-2007	Harbor Logistics Center ZB-2026-017	Northwind Structures 410 Ironworks Drive, Marion, OH 43302	23 October 2026	27 October 2026

Steel delivery resequencing and revised office glazing

Northwind Structures requests the following change to the Work under the Agreement dated 18 June 2026 for Harbor Logistics Center, project ZB-2026-017. Zava Builders accepts the stated scope, phase-specific calendar-day adjustments and net price upon the acceptance recorded below; the detailed description in this document is attached to and forms part of this change order.

Change 1 · Phase 2: Structural frame

As contracted	As changed by this change order
• Fabricate and erect approximately 1,150 tons of ASTM A992 structural steel to S-201 through S-206 and AISC 360. • Provide the W24x76 north office roof beams shown on S-205 with the originally approved member sizes and connection details. • Erect the north office block followed by warehouse bays 1 to 8 in the sequential delivery and crane plan on S-601. • Maintain the 36 ft warehouse clear height and inspect bolted connections under the RCSC Specification for Structural Joints Using High-Strength Bolts.	• Retain approximately 1,150 tons of ASTM A992 steel, the W24x76 office roof beams, all member grades and approved connection requirements. • Revise S-601 erection and delivery planning to erect warehouse bays 1 to 8 ahead of the north office block while the office beams are in transit. • Receive and stage the delayed W24x76 members separately and complete office block erection last after those members reach the site. • Maintain the warehouse clear height, temporary stability checks and original connection inspection requirements throughout the revised sequence.

Added work

- Prepare a revised delivery, lifting and temporary stability plan covering warehouse bays 1 to 8 and the deferred north office block.
- Re-sort and re-mark warehouse bay delivery bundles so that crane operations continue on the warehouse frame while office steel is in transit.
- Provide a protected staging area and an additional handling cycle for the delayed W24x76 office roof beam delivery.
- Reposition the crane and erection crew for the office block after completion of the priority warehouse bays.

- Repeat alignment and connection release checks at the revised office-to-warehouse handover before removing temporary restraints.

Deleted work

- Delete the originally planned north-office-first delivery and lifting sequence under S-601; no permanent structural steel is deleted.

Work that remains as contracted

- All permanent member sizes, steel grades, connections and roof deck requirements remain as contracted.
- Warehouse bays retain their original completion basis; the identified extension concerns completion of the office block within the frame phase.
- The 36 ft warehouse clear height and all 40 dock opening framing requirements remain unchanged.

Reason

Mill rolling date for the W24x76 roof beams moved from 5 October to 19 October; the office block steel is the last erected and cannot be completed until those members are on site. The revised sequence uses available warehouse steel to keep the erection crane productive, but the north office roof cannot be completed before the delayed members arrive. This is a logistics and erection-sequence change without a structural redesign.

Schedule impact on this phase: 10 calendar days against the existing schedule

The scheduled duration of Phase 2, Structural frame, increases by ten (10) calendar days against the existing schedule. The mill rolling date for the W24x76 office roof beams moved from 5 October to 19 October. Erecting warehouse bays 1 to 8 while those beams are in transit keeps the crane working, but the office block, erected last, completes ten days later than the existing frame schedule. Warehouse bays are unaffected. This is the Phase 2 adjustment only; no revised date or dependent-phase extension is stated here.

Cost

Item	Amount
Labor: 1 erection crew of 6 persons for resequencing, additional rigging and office-block remobilisation over 5 shifts	$12,000
Equipment: crane repositioning, additional rigging and telehandler handling for the delayed W24x76 delivery	$7,000
Delivery coordination: revise 8 warehouse bay load releases, re-mark bundles and supervise the separate office-beam staging area	$3,000
Change in contract sum for this phase	**$22,000**

Change 2 · Phase 5: Envelope and glazing

As contracted	As changed by this change order

• Provide approximately 4,800 sq ft of north office curtain wall with nominal 1 inch insulated glass units to A-401 and ASTM E2190. • Use the original thermally broken ASTM B221 aluminum mullion sections shown on A-402 for the specified double-glazed assembly. • Procure the original office insulated glazing as a 7-week lead item after approved release under specification 08 44 13. • Install perimeter seals to ASTM C920 and verify installed curtain-wall air and water performance by ASTM E783 and ASTM E1105.	• Provide approximately 4,800 sq ft of north office curtain wall with 1-3/8 inch triple-glazed insulated units incorporating a warm-edge spacer under revised A-401 and ASTM E2190. • Increase the depth of the original A-402 mullion sections by 4 inches, retaining thermally broken ASTM B221 aluminum framing and revising the support calculations. • Procure the triple-glazed units as a 9-week lead item after revised shop-drawing approval, in place of the original 7-week units. • Retain ASTM C920 perimeter seals and field air and water testing, with revised gaskets, anchors and interfaces coordinated to the approved deeper assembly.

Added work

- Revise curtain-wall shops, glass makeups and structural calculations for the 4,800 sq ft north office glazing area and deeper mullion profiles.
- Procure 1-3/8 inch triple-glazed units with warm-edge spacers to replace the specified 1 inch units at each scheduled office opening.
- Fabricate mullions 4 inches deeper than the original sections and coordinate revised anchor stand-offs and perimeter trim interfaces.
- Provide compatible revised glazing gaskets, setting blocks and perimeter seals for the increased unit thickness.
- Install and test a representative revised office bay before completing repetitive glazing installation.

Deleted work

- Delete the nominal 1 inch office insulated glass units from the affected 4,800 sq ft curtain-wall area.
- Delete the original mullion profiles, glazing gaskets and interface trims only where superseded by the revised deeper assembly; pricing includes the original component credits.

Work that remains as contracted

- Warehouse insulated metal panels, roof membrane and all 40 dock exterior closure assemblies remain as contracted.
- Office opening locations and nominal curtain-wall area remain unchanged.
- Safety-glazing requirements and the original field air leakage and water penetration acceptance procedures remain applicable.

Reason

Owner's energy consultant requested the triple-glazed assembly to meet the revised envelope performance target for the office block. The thicker units and deeper supporting members require a coordinated resubmittal before fabrication so the revised energy target is met without compromising anchorage, drainage or perimeter sealing.

Schedule impact on this phase: 14 calendar days against the existing schedule

The scheduled duration of Phase 5, Envelope and glazing, increases by fourteen (14) calendar days against the existing schedule once this phase starts. Triple-glazed units have a 9-week lead time against 7 weeks for the specified units, and the deeper mullions require revised shop drawings before fabrication release. These procurement and coordination requirements make the office envelope work take two weeks longer. This phase-specific adjustment is separate from the Phase 2 frame adjustment; no new date is stated.

Cost

Item	Amount
Materials: net upgrade for 4,800 sq ft of 1-3/8 inch triple glazing, warm-edge spacers and mullions 4 inches deeper, including credit for deleted 1 inch units and original framing	$26,000
Labor: 1 glazing crew of 4 persons for revised setting, deeper-frame interfaces and representative bay testing over 4 shifts	$6,000
Engineering and shops: revise office curtain-wall elevations, glass makeups, anchor calculations and fabrication details for the 4,800 sq ft assembly	$3,000
Change in contract sum for this phase	**$35,000**

Summary of this change order

Phases changed: Phase 2, Phase 5. Schedule impact: 24 calendar days in total across the changed phases, each against its own existing schedule. Change in contract sum: $57,000.

Phases that depend on a changed phase are adjusted in the project schedule record after acceptance; their managers are notified by the Contractor.

Contract sum and contract time

Original contract sum	$8,100,000
Net change by previously accepted change orders	$0
Contract sum prior to this change order	$8,100,000
This change order	$57,000
New contract sum	**$8,157,000**

Contract time: The scheduled duration of Phase 2 is increased by ten (10) calendar days; the scheduled duration of Phase 5 is increased by fourteen (14) calendar days. After acceptance, Zava Builders adjusts the dates of dependent phases in the Schedule Record under the existing dependencies and notifies their vendors in writing. The two phase-specific adjustments are recorded separately and do not, by themselves, state a total project extension.

Terms

- Upon authorised acceptance, this change order amends the Agreement only for the work, phase-specific time adjustments and Contract Sum adjustment expressly stated herein.
- The net adjustment is full compensation for this change, including additions, deletions, coordination, overhead and profit; no separate duplicate recovery is due for the stated changed work.
- After acceptance, Zava Builders shall adjust dependent phases in the Schedule Record according to existing dependencies and notify the affected vendors in writing; the phase-specific adjustments do not independently establish a revised project completion date.
- Pricing is valid for 30 days from submission.
- Except as expressly amended, all other Agreement terms, scope requirements, inspections and warranties remain unchanged.
- The detailed as-contracted, as-changed, added, deleted and unchanged work descriptions, reasons, schedule impacts and cost breakdowns above constitute the attached description and are integral to this change order.

Submitted by
Grace Lindqvist, Project Executive,
Northwind Structures
23 October 2026

Accepted for Zava Builders by
Anissa Carvalho, Project Manager,
Zava Builders
27 October 2026

All companies, people, addresses and figures in this document are fictional, created for a product demonstration.