Zava Builders · 1200 Granite Way, Suite 400, Columbus, OH 43215 · 614-555-0142

Change Order

CO-4015 · Northgate Distribution Hub (ZB-2026-019)

Change order	Project	Vendor	Submitted	Accepted
CO-4015	Northgate Distribution Hub ZB-2026-019	Contoso Concrete 88 Quarry Road, Delaware, OH 43015	24 October 2026	28 October 2026

Additional rock excavation at the north retaining wall

Contoso Concrete requests the following change to the Work under the Agreement for this project, whose execution date is not specified in this change order for Northgate Distribution Hub, project ZB-2026-019. Zava Builders accepts the stated scope, phase-specific calendar-day adjustments and net price upon the acceptance recorded below; the detailed description in this document is attached to and forms part of this change order.

Change 1 · Phase 1: Site work and foundations

As contracted	As changed by this change order
• Excavate the north retaining-wall footing to the lines and bearing elevation shown on S-101 and the geotechnical profile referenced by C-101. • Remove ordinary excavation material above the reported rock surface and prepare a clean, stable footing formation to specification 31 20 00. • Construct the north retaining-wall footing with 4,000 psi reinforced concrete and ASTM A615 Grade 60 reinforcement to S-102 and ACI 318. • Protect adjoining excavation faces and maintain drainage during footing preparation under C-301 and the approved excavation safety plan.	• Retain the north retaining-wall alignment, footing dimensions and design bearing elevation on S-101 and S-102. • Excavate and remove an additional 640 cubic yards of unforeseen rock encountered 2.5 ft above the geotechnical profile elevation. • Use a hydraulic breaker to reduce the additional rock within the approved excavation limits, then trim and clean the original design footing formation. • Retain the original 4,000 psi footing concrete, ASTM A615 Grade 60 reinforcement and excavation protection requirements.

Added work

- Survey and jointly measure the unforeseen rock boundary and the additional 640 cubic yards before removal.
- Mobilise an excavator-mounted hydraulic breaker and break the additional rock in controlled lifts within the north footing excavation.
- Load, haul and dispose of approximately 640 cubic yards of in-place rock volume at an approved receiving location, accounting for loose-volume swell in haul planning.
- Trim the exposed formation, remove loose fragments and maintain drainage for footing bearing

inspection.

- Provide additional equipment exclusion barriers and condition checks of adjacent excavation faces during the breaker operation.

Deleted work

- None.

Work that remains as contracted

- The north retaining-wall alignment, footing geometry and final bearing elevation remain as contracted.
- Footing concrete strength, reinforcement and anchor details remain unchanged.
- Ordinary excavation quantities already in the Agreement remain included; the stated adjustment covers only the additional unforeseen rock.

Reason

Rock encountered 2.5 ft above the elevation shown in the geotechnical report. The higher rock surface creates additional hard excavation within the original footing limits. The extra hydraulic breaking and removal are required to expose the original design formation without moving or redesigning the retaining wall.

Schedule impact on this phase: 7 calendar days against the existing schedule

The scheduled duration of Phase 1, Site work and foundations, increases by seven (7) calendar days against the existing schedule. Hydraulic breaker removal of the additional 640 cubic yards of rock, followed by trimming, haulage and bearing-surface inspection, adds one week to the site work phase. The stated extension applies to Phase 1 only; no revised date or unverified dependent-phase relationship is stated.

Cost

Item	Amount
Labor: 1 excavation crew of 4 persons for 7 shifts, including rock measurement, breaker support, formation trimming and protection	$24,000
Equipment: excavator with hydraulic breaker, loading excavator and pumps for the additional 640 cubic yards of rock removal	$27,000
Hauling and disposal: load, transport and receive 640 cubic yards of in-place rock, including allowance for loose-volume swell	$10,000
Change in contract sum for this phase	**$61,000**

Summary of this change order

Phases changed: Phase 1. Schedule impact: 7 calendar days in total across the changed phases, each against its own existing schedule. Change in contract sum: $61,000.

Phases that depend on a changed phase are adjusted in the project schedule record after acceptance; their managers are notified by the Contractor.

Contract sum and contract time

Original contract sum	$5,250,000
Net change by previously accepted change orders	$0
Contract sum prior to this change order	$5,250,000
This change order	$61,000
New contract sum	**$5,311,000**

Contract time: The scheduled duration of Phase 1 is increased by seven (7) calendar days. After acceptance, Zava Builders adjusts the dates of dependent phases in the Schedule Record under the existing dependencies and notifies their vendors in writing.

Terms

- Upon authorised acceptance, this change order amends the Agreement only for the work, phase-specific time adjustments and Contract Sum adjustment expressly stated herein.
- The net adjustment is full compensation for this change, including additions, deletions, coordination, overhead and profit; no separate duplicate recovery is due for the stated changed work.
- After acceptance, Zava Builders shall adjust dependent phases in the Schedule Record according to existing dependencies and notify the affected vendors in writing; the phase-specific adjustments do not independently establish a revised project completion date.
- Pricing is valid for 30 days from submission.
- Except as expressly amended, all other Agreement terms, scope requirements, inspections and warranties remain unchanged.
- The detailed as-contracted, as-changed, added, deleted and unchanged work descriptions, reasons, schedule impacts and cost breakdowns above constitute the attached description and are integral to this change order.

Submitted by
Luis Herrera, Operations Manager,
Contoso Concrete
24 October 2026

Accepted for Zava Builders by
Anissa Carvalho, Project Manager,
Zava Builders
28 October 2026

All companies, people, addresses and figures in this document are fictional, created for a product demonstration.