Agreement for Construction Services

Project ZB-2026-014 · Riverside Corporate Office · 2400 Riverside Drive, Columbus, OH 43221

Agreement date: 12 May 2026
Contractor: Zava Builders, 1200 Granite Way, Suite 400, Columbus, OH 43215
Project: Riverside Corporate Office (ZB-2026-014)
Contract sum: $6,400,000 **Planned completion:** 12 March 2027

Recitals

This Agreement dated 12 May 2026 is made between the Owner and Zava Builders, general contractor, for Riverside Corporate Office, project ZB-2026-014, at 2400 Riverside Drive, Columbus, OH 43221.

Four-storey, 92,000 sq ft corporate headquarters office with structured parking at grade, a two-storey atrium lobby, and open-plan floors with conference suites on levels 2 to 4. The Owner engages Zava Builders to execute the following stipulated-sum construction scope and coordinate its phase handovers.

Definitions

- Agreement: This executed construction agreement, its referenced drawings and specifications, the Schedule Record and subsequently accepted written change orders.
- Work: All construction, procurement, temporary measures, testing, coordination and closeout obligations necessary to deliver the project scope described in this Agreement.
- Phase: A numbered scope allocation with its designated vendor, fixed dates, cost and explicit predecessor, if any, as set out in Section 2 and the Schedule Record.
- Schedule Record: The controlling written record of phase dates and explicit dependencies; amendments require accepted written change orders and contractor coordination of dependent phases.
- Change Order: A written instrument identifying the contracted and changed work, additions and deletions, phase-specific calendar-day adjustment and Contract Sum adjustment accepted by the authorised parties.
- Owner: The commissioning party executing this Agreement through its authorised signatory; trade vendors are subcontracting participants and are not parties signing this Agreement.

1. The Work

Zava Builders shall furnish and coordinate labour, materials, equipment, supervision, permits, inspection attendance and closeout documentation necessary to deliver Riverside Corporate Office for the Owner in accordance with this Agreement. Particular coordination obligations concern office floor finishes, atrium interfaces and conference-suite coordination.

The contract documents comprise this Agreement, the approved civil, structural, architectural and

trade drawings referenced below, the specifications and the Schedule Record. Referenced standards establish material and workmanship requirements; applicable adopted code requirements govern where more stringent. Resolve inconsistent dimensions and requirements by written request to the Owner before affected work proceeds.

- Protect adjoining property, existing services, survey controls and accepted work; provide temporary access, barriers and housekeeping throughout construction.
- Quantities stated in the phase descriptions are approximate scope allowances for this stipulated-sum Agreement; final installed dimensions follow the approved drawings, and scope alterations require a written change order.
- Maintain coordinated record drawings and inspection records by phase; include required testing and correction of nonconforming work in the stated phase allocations.

2. Scope of Work by Phase

Phase	Vendor	Depends on	Start	End	Cost
1 · Site work and foundations	Contoso Concrete	—	1 June 2026	10 July 2026	$820,000
2 · Structural frame	Northwind Structures	—	13 July 2026	4 September 2026	$1,450,000
3 · Concrete floors and slabs	Contoso Concrete	Phase 1	14 September 2026	6 November 2026	$980,000
4 · Interior build-out	Wingtip Interiors	Phase 3	16 November 2026	22 January 2027	$1,620,000
5 · Envelope and glazing	Northwind Structures	Phase 2	14 September 2026	20 November 2026	$1,130,000
6 · Fit-out and furniture	Litware Workplace	Phase 4	1 February 2027	12 March 2027	$400,000

Phase 1 · Site work and foundations — Contoso Concrete

Contoso Concrete shall perform Site work and foundations from 1 June 2026 through 10 July 2026 for $820,000; this phase shall establish the office bearing platform, atrium foundations and at-grade parking interfaces before the slab handover.

Work items

- Survey the 92,000 sq ft building floor-area layout and establish foundation offsets and protected benchmarks to C-101 and S-101.
- Strip approximately 1,900 cubic yards of topsoil from the building and parking work limits to C-102; stockpile separately from structural fill.
- Excavate approximately 4,800 cubic yards for spread footings, grade beams and atrium pits to S-101 and S-102.
- Place approximately 2,600 cubic yards of engineered fill in maximum 8 inch loose lifts to C-103 and ASTM D1557 compaction criteria.

- Install approximately 1,100 linear feet of perforated foundation drain with washed aggregate and filter fabric to C-301.
- Place approximately 1,250 cubic yards of 4,000 psi reinforced foundation concrete to S-101 through S-104 and ACI 318.
- Set approximately 140 anchor-rod assemblies and coordinate atrium column base templates to S-104 and ASTM F1554.
- Construct approximately 420 linear feet of parking-edge grade beam and isolate adjacent pavement joints to S-103 and C-401.
- Backfill foundation walls and restore positive drainage away from the office footprint to C-103.

Materials and standards

- Structural fill shall be well-graded crushed aggregate free of organics, classified by ASTM D2487 and compacted to at least 95% of ASTM D1557 maximum dry density.
- Foundation concrete shall have 4,000 psi specified compressive strength, ASTM C150 cement and ASTM C33 aggregates; reinforcement shall be ASTM A615 Grade 60 under ACI 318.
- Foundation drain shall use nominal 4 inch perforated PVC meeting ASTM D2729 with nonwoven filter fabric and washed drainage stone.
- Anchor rods shall be ASTM F1554 Grade 55 with compatible nuts, washers and templates; exposed finishes shall follow S-104.

Submittals, testing and inspection

- Submit earthwork methods, foundation reinforcing shop drawings and concrete mix designs to Zava Builders for Owner review before placement.
- Have the independent testing agency witness bearing surfaces and perform ASTM D6938 field density tests; Zava Builders shall witness failed-area retests before covering.
- Have the independent testing agency sample fresh concrete under ASTM C172, measure slump under ASTM C143 and make ASTM C31 specimens for ASTM C39 strength tests.
- Submit anchor-rod survey records and footing inspection releases, witnessed by Zava Builders and the Owner's representative, before backfill.

Exclusions

- Structural steel and deck erection belong to Structural frame.
- Floor slab placement and floor finishing belong to Concrete floors and slabs.

This phase has no predecessor in the Schedule Record; it may begin on its fixed start subject to notice to proceed and safe release of its work area.

Phase 2 · Structural frame — Northwind Structures

Northwind Structures shall perform Structural frame from 13 July 2026 through 4 September 2026 for $1,450,000; this phase shall deliver the four-storey office skeleton, atrium framing and deck supports for the subsequent envelope and floor trades.

Work items

- Detail and erect approximately 720 tons of structural steel for the four-storey office to S-201 through S-204 and AISC 360.
- Provide ASTM A992 wide-flange columns and beams on the office grid shown on S-201.
- Frame the two-storey atrium opening with perimeter girders and lateral restraints to S-202 and

S-501.

- Install approximately 69,000 sq ft of composite floor deck above grade, nominal 3 inch profile, to S-301 and ASTM A653.
- Install approximately 23,000 sq ft of roof deck and perimeter closures to S-304 and the approved deck fastening schedule.
- Erect two stair framing assemblies with landing supports to S-401 and AISC 303.
- Provide conference-suite opening trimmers on levels 2 to 4 and shaft edge angles to S-203 and S-204.
- Install slip-critical bracing connections and pretension bolts to S-502 and the RCSC Specification for Structural Joints Using High-Strength Bolts.
- Survey column plumbness and deck elevations at each level to the tolerances of AISC 303.

Materials and standards

- Wide-flange members shall be ASTM A992; hollow structural sections shall be ASTM A500 Grade C, detailed under AISC 360.
- Connection plates shall be ASTM A36 unless a higher grade is scheduled; bolts shall meet ASTM F3125 Grade A325 with matching nuts and hardened washers.
- Floor and roof deck shall be galvanised ASTM A653 steel of the profile and base-metal thickness scheduled on the structural drawings.
- Shop and field welds shall conform to AWS D1.1; fabrication and erection tolerances shall conform to AISC 303.

Submittals, testing and inspection

- Submit member shop drawings, connection calculations, erection bracing and deck fastening plans for review by the Owner's structural reviewer through Zava Builders.
- Provide mill certificates and bolt lot certificates before erection; the independent special inspector shall verify member identification and connection materials.
- Have the independent special inspector witness bolt pretension verification and inspect welds under AWS D1.1, including nondestructive examination where the structural inspection schedule requires it.
- Submit signed alignment surveys, deck fastening inspection records and corrected connection reports for Owner and Zava Builders acceptance.

Exclusions

- Concrete topping and ground-bearing slabs belong to Concrete floors and slabs.
- Curtain-wall glazing and weather seals belong to Envelope and glazing.

This phase has no predecessor in the Schedule Record; it may begin on its fixed start subject to notice to proceed and safe release of its work area.

Phase 3 · Concrete floors and slabs — Contoso Concrete

Contoso Concrete shall perform Concrete floors and slabs from 14 September 2026 through 6 November 2026 for $980,000; this phase shall deliver the office floor plates and atrium slab with the original sealed broom finish, ready for the specified interior flooring allowance.

Work items

- Prepare approximately 23,000 sq ft of ground-floor subbase with a 6 inch compacted aggregate

layer to S-105 and ASTM D1557.

- Install a nominal 15 mil vapor retarder below the ground-bearing office slab to S-105 and ASTM E1745.
- Place approximately 92,000 sq ft of 4,000 psi reinforced concrete floors across levels 1 to 4, including the atrium floor, to S-301 through S-304 and ACI 318.
- Provide nominal 5 inch ground-bearing slab and elevated slab depths over composite deck as scheduled on S-301 through S-304.
- Finish the 92,000 sq ft floor area with a sealed broom-finish surface under A-601 and ACI 302.1R; the original interior schedule includes resilient flooring above this substrate.
- Sawcut ground-slab contraction joints on nominal 15 ft panels and form column isolation joints to S-105 and ACI 302.1R.
- Install approximately 240 linear feet of slab-edge blockouts and coordinate service penetrations to S-305.
- Cure slabs using the approved moisture-retention method to ACI 308.1 and protect surfaces from construction traffic.
- Verify surface elevations, substrate compatibility and readiness for resilient flooring under A-601 and ASTM F710.

Materials and standards

- Floor concrete shall be 4,000 psi normal-weight concrete with ASTM C150 cement and ASTM C33 aggregate, proportioned under ACI 301.
- Reinforcing bars shall be ASTM A615 Grade 60; welded wire reinforcement, where detailed, shall meet ASTM A1064.
- Below-slab vapor retarder shall be nominal 15 mil ASTM E1745 Class A with compatible sealed joints and penetrations.
- Joint sealant shall meet ASTM C920; curing materials and finish treatments shall be compatible with the scheduled final floor system under ACI 308.1.

Submittals, testing and inspection

- Submit placement plans, mix designs, reinforcement shops, curing method and finish samples through Zava Builders to the Owner before slab placement.
- Have the independent testing agency measure slump to ASTM C143, air content to ASTM C231 and strength using ASTM C31 specimens tested under ASTM C39; Zava Builders shall witness sampling.
- Submit joint layout surveys and finish acceptance records to Zava Builders and the Owner before releasing the surfaces to following trades.
- Have the independent testing agency document ASTM F2170 moisture results where resilient flooring is scheduled and report substrate readiness to the Owner's representative.

Exclusions

- Foundation earthwork and footing concrete belong to Site work and foundations.
- Resilient flooring, partitions and ceiling finishes belong to Interior build-out.

This phase depends on Phase 1, Site work and foundations, and cannot begin until that predecessor is accepted as complete.

Phase 4 · Interior build-out — Wingtip Interiors

Wingtip Interiors shall perform Interior build-out from 16 November 2026 through 22 January 2027 for $1,620,000; this phase shall form the open-plan offices and conference suites around the completed floor plates, including the original resilient flooring allowance.

Work items

- Frame approximately 18,000 sq ft of partition surface at conference suites on levels 2 to 4 to A-201 through A-204 and ASTM C754.
- Install nominal 5/8 inch gypsum board on office and atrium partitions to A-501 and ASTM C840.
- Provide rated shaft and corridor assemblies with full-height perimeter seals to A-502 and ASTM E119 tested assemblies.
- Install approximately 110 door and hardware sets to A-701 and the specified NFPA 80 requirements at rated openings.
- Install approximately 72,000 sq ft of suspended acoustical ceiling panels and atrium perimeter closures to A-601 and ASTM C636.
- Carry the original resilient flooring allowance over the 92,000 sq ft slab finish area on levels 1 to 4, including the atrium, under A-601 and ASTM F710 substrate preparation requirements.
- Apply washable wall coatings over approximately 38,000 sq ft of prepared wall surface to A-602 and ASTM D2486 performance criteria.
- Provide conference-suite acoustic insulation and sealed perimeter joints to A-503 and ASTM C665.
- Install casework backing, access panels and service opening trims to A-504 while preserving clear routes through the atrium.

Materials and standards

- Non-loadbearing steel studs shall meet ASTM C645; gypsum board shall meet ASTM C1396 with Type X board in the specified rated assemblies.
- Acoustic insulation shall be ASTM C665 mineral fiber; perimeter sealants shall meet ASTM C920 and rated firestop systems shall have ASTM E814 test evidence.
- Suspended ceiling grids shall meet ASTM C635 and be installed to ASTM C636; panel properties shall match the room finish schedule.
- Resilient flooring shall meet ASTM F1303; washable coatings shall have ASTM D2486 scrub-resistance data and substrate preparation shall follow ASTM F710 where flooring is applied.

Submittals, testing and inspection

- Submit partition shops, rated-assembly listings, reflected ceiling coordination and finish samples to Zava Builders for Owner approval.
- Have Zava Builders and the Owner's representative inspect backing, firestops and above-ceiling work before concealment; record deficiencies and closure evidence.
- Construct a representative room finish mockup and have the Owner witness cleanability, door operation and accessible clearances before repetitive installation.
- Submit substrate moisture records and flooring adhesion checks required by the approved product instructions before area acceptance.

Exclusions

- Structural slab placement and curing belong to Concrete floors and slabs.
- Movable furniture and scheduled exam-room or workplace casework belong to Fit-out and furniture.

This phase depends on Phase 3, Concrete floors and slabs, and cannot begin until that predecessor is accepted as complete.

Phase 5 · Envelope and glazing — Northwind Structures

Northwind Structures shall perform Envelope and glazing from 14 September 2026 through 20 November 2026 for $1,130,000; this phase shall close the office perimeter and atrium with a drained curtain-wall and insulated opaque envelope.

Work items

- Install approximately 34,000 sq ft of thermally broken aluminum curtain wall to A-301 through A-304 and the approved structural calculations.
- Glaze approximately 22,000 sq ft with nominal 1 inch insulated glass units to A-401 and ASTM E2190.
- Provide approximately 12,000 sq ft of insulated opaque wall assemblies and panel attachments to A-305 and ASTM C1289 insulation requirements.
- Install approximately 2,000 linear feet of continuous perimeter air and water seals to A-402 and ASTM C920.
- Form approximately 900 linear feet of sill flashing with end dams and drained weeps to A-403.
- Install the two-storey atrium entrance glazing and overhead framing interfaces to A-404 and ANSI Z97.1 safety glazing requirements.
- Provide perimeter fire containment at elevated slab edges to A-405 and ASTM E2307 tested systems.
- Close approximately 23,000 sq ft of roof area with single-ply membrane and tapered insulation to A-901 and ASTM D6878.
- Complete field water penetration and air leakage checks at representative office bays to ASTM E1105 and ASTM E783.

Materials and standards

- Curtain-wall framing shall use ASTM B221 aluminum extrusions with thermally separated profiles and the finish specified on A-401.
- Insulated glass units shall have ASTM E2190 qualification; glass shall meet ASTM C1036 and heat-treated glass shall meet ASTM C1048.
- Safety glazing at hazardous locations shall comply with ANSI Z97.1; perimeter elastomeric sealants shall comply with ASTM C920.
- Roof membrane shall meet ASTM D6878 and polyisocyanurate roof insulation shall meet ASTM C1289; attachment shall follow the approved uplift calculations.

Submittals, testing and inspection

- Submit curtain-wall shops, glass makeups, anchorage calculations, sealant compatibility evidence and roof attachment calculations for Owner review through Zava Builders.
- Have the independent testing agency perform ASTM E783 air leakage and ASTM E1105 water penetration tests on representative installed bays witnessed by Zava Builders and the Owner.
- Have Zava Builders witness air-barrier transitions and concealed sill flashings before closure; document sealant adhesion checks to ASTM C1521.
- Submit glazing certificates, roof seam inspection logs and corrected leak-test records before envelope acceptance.

Exclusions

- Primary steel framing belongs to Structural frame.
- Internal partitions, room finishes and ceilings belong to Interior build-out.

This phase depends on Phase 2, Structural frame, and cannot begin until that predecessor is accepted as complete.

Phase 6 · Fit-out and furniture — Litware Workplace

Litware Workplace shall perform Fit-out and furniture from 1 February 2027 through 12 March 2027 for $400,000; this phase shall equip the open-plan office floors, conference suites and reception after interior acceptance.

Work items

- Supply and assemble approximately 320 workstations across levels 1 to 4 to A-801 through A-804 and ANSI/BIFMA X5.5.
- Install approximately 320 task chairs with adjustable mechanisms to A-805 and ANSI/BIFMA X5.1.
- Provide approximately 24 conference tables for suites on levels 2 to 4 to A-806 and ANSI/BIFMA X5.5.
- Install approximately 160 storage cabinets with wall restraints at designated positions to A-807 and ANSI/BIFMA X5.9.
- Set a nominal 24 linear ft reception counter with accessible transaction position to A-808 and ICC A117.1.
- Provide approximately 80 reception and meeting seats to A-805 and ANSI/BIFMA X5.4.
- Install workstation cable-management trays and grommets at the approved service positions to A-809; leave electrical terminations to the authorised service trade.
- Anchor fixed furniture using substrate-specific fasteners and verify circulation clearances to A-810 and ICC A117.1.
- Adjust moving parts and furnish itemised furniture inventories and care instructions to specification 12 50 00.

Materials and standards

- Casework shall conform to ANSI/AWI 0641 with high-pressure decorative laminate meeting the applicable ANSI/NEMA LD 3 grade for the scheduled surfaces.
- Work surfaces shall use sealed edges, moisture-resistant cores where scheduled and hardware meeting ANSI/BHMA A156.9.
- Task chairs shall have ANSI/BIFMA X5.1 performance documentation; tables and desks shall have ANSI/BIFMA X5.5 documentation.
- Storage units shall have ANSI/BIFMA X5.9 documentation; lounge and waiting seating shall have ANSI/BIFMA X5.4 documentation.

Submittals, testing and inspection

- Submit dimensioned casework and furniture layouts, finish samples, anchorage details and product performance certificates to Zava Builders for Owner approval.
- Field-measure completed rooms and service positions with Zava Builders before fabrication release; record discrepancies against the approved layouts.
- Have the Owner's representative and Zava Builders witness a representative installed furniture

group, accessible clearances, anchorage and moving-part operation.
- Deliver itemised inventories, care instructions and warranty certificates with a jointly witnessed room-by-room punch list.

Exclusions

- Clinical or office partitions, flooring and casework backing belong to Interior build-out.
- Structural slab preparation and concrete placement belong to Concrete floors and slabs.

This phase depends on Phase 4, Interior build-out, and cannot begin until that predecessor is accepted as complete.

3. Schedule

Planned completion of Riverside Corporate Office is 12 March 2027, the latest phase end in the Schedule Record. Phase dates are fixed in the Schedule Record and change only by written change order.

Sequence the Work to protect office floor finishes, atrium interfaces and conference-suite coordination. The dependency statements in Section 2 reproduce the agreed predecessor relationships; a later completion of one independent activity does not automatically amend another activity's dates.

- The Owner shall issue written notice to proceed before site mobilisation; the notice does not alter any phase date fixed in the Schedule Record.
- Float is a shared project resource administered by Zava Builders for the benefit of timely completion; use of float alone creates no entitlement to additional compensation.
- Ordinary seasonal weather is included in the fixed dates; exceptional weather requires contemporaneous daily records, prompt written notice and an accepted written change order for any time adjustment.
- Phase acceptance requires inspection releases, corrected defects affecting follow-on work and written acceptance by Zava Builders with the Owner; progress payment alone does not establish acceptance.
- Only the expressly listed predecessor governs a phase dependency; safe work-area releases and inspection hold points remain mandatory for concurrent activities without creating additional Schedule Record links.
- Liquidated damages are $1,500 per calendar day of unexcused delay beyond the contract completion date, as adjusted by accepted written change order; the parties agree this is a reasonable estimate of delay-related administrative and occupancy costs.

4. Contract Sum and Payment

The Owner shall pay Zava Builders the stipulated contract sum of six million four hundred thousand dollars ($6,400,000), equal to the sum of all phase allocations in the schedule of values below.

Submit monthly progress payment applications identifying completed work by phase, properly stored materials supported by title and insurance evidence, prior payments and approved changes. The Owner shall review quantities, inspection records and supporting invoices and pay approved amounts monthly, subject to retainage of 5% from each approved progress amount.

Release retainage only after final acceptance, correction of outstanding deficiencies, delivery of

warranties and record documents, and evidence of payment of subcontractors and suppliers. Payment does not waive defective work or replace written phase acceptance.

- Phase 1, Site work and foundations: $820,000.
- Phase 2, Structural frame: $1,450,000.
- Phase 3, Concrete floors and slabs: $980,000.
- Phase 4, Interior build-out: $1,620,000.
- Phase 5, Envelope and glazing: $1,130,000.
- Phase 6, Fit-out and furniture: $400,000.

5. Changes in the Work

A written change order shall identify the affected phase and describe the Work as contracted and as changed, separately stating added work, deleted work and unchanged adjacent work. It shall state the change in that phase's scheduled duration in calendar days, with the reason and sequencing basis, and the change in the Contract Sum, including a zero adjustment where appropriate.

Each change order shall show the original Contract Sum, the net change by previously accepted change orders, the Contract Sum before this change order, the amount of this change order and the new Contract Sum. Supporting cost detail shall distinguish labour, materials, equipment and applicable credits; the accepted amount includes overhead and profit.

The Owner and Zava Builders shall authorise changes in writing; a vendor submission becomes binding only upon authorised acceptance. Zava Builders shall confirm Owner authorisation before accepting a vendor change that amends this Agreement. No oral direction changes the Contract Sum or phase dates.

After acceptance, Zava Builders shall adjust dependent phases in the Schedule Record in accordance with the stated dependencies and notify their vendors in writing. A phase-specific extension is recorded once against its identified phase; resulting predecessor effects are assessed through the Schedule Record rather than assigned as duplicate extensions.

- Preserve the original scope and schedule basis with each accepted change order and retain supporting quantities and approvals.
- Proceed with unaffected work while a change is under review, subject to safe access and the existing inspection hold points.

6. General Conditions

The following conditions apply to all Work at Riverside Corporate Office, including coordinated attendance during turnover.

- Maintain commercial general liability insurance of $2,000,000 per occurrence and $4,000,000 aggregate, automobile liability of $1,000,000 combined single limit, statutory workers compensation and employers liability of $1,000,000; provide certificates before mobilisation and name the Owner as additional insured where applicable.
- Furnish performance and payment bonds each in the amount of 100% of the Contract Sum, with adjustments for accepted changes; maintain the bonds through the required completion and payment obligations.

- Warrant materials and workmanship for one year from documented substantial completion, promptly correct covered defects on written notice and transfer longer product warranties to the Owner.
- Zava Builders shall direct site safety, implement OSHA construction safety requirements, maintain fall protection, excavation protection and controlled access, and coordinate the safety responsibilities of all trades.
- Substantial completion requires lawful occupancy or intended use, required inspections and operational life-safety systems; final completion requires all corrective work, record documents, training, warranties and final payment releases accepted by the Owner.
- Resolve disputes first through documented discussions between authorised representatives, then mediation; unresolved claims may be brought in a court of competent jurisdiction, while undisputed safe work continues.
- Ohio law governs this Agreement and its interpretation, subject to applicable mandatory public-works requirements and the approved permits.
- Send contractual notices in writing to the Owner through its authorised signatory and to Zava Builders, attention Robert Okonkwo, Director of Preconstruction and Contracts, at 1200 Granite Way, Suite 400, Columbus, OH 43215; retain evidence of receipt and identify the project and affected phase.

7. Signatures

Executed for Zava Builders by Robert Okonkwo, Director of Preconstruction and Contracts. Signature: _____. Date: _____.

Executed for the Owner by its authorised signatory. Name and title: _____. Signature: _____. Date: _____.

For the Contractor
Robert Okonkwo, Director of Preconstruction and Contracts
Zava Builders

For the Owner
Authorised signatory
Date

Zava Builders, its projects, vendors, people and figures are fictional, created for a product demonstration.